



SIMEC Mining:

**Tahmoor North Western Domain
Longwalls West 1 and West 2**

Management Plan for Potential Impacts to No. 675 Thirlmere Way (Mill Hill)

AUTHORISATION OF MANAGEMENT PLAN

Authorised on behalf of Tahmoor Coal:

Name: Zina Ainsworth.

Signature: 

Position: Environment & Community Manager

Date: 28 July 2020

Authorised on behalf of Mill Hill:

Name:

Signature:

Position:

Date:

DOCUMENT REGISTER

Date	Report No.	Rev	Comments
Apr-18	MSEC862-13-02	A	Draft for review for LWs 31 and 32
May-18	MSEC862-13-02	B	Final Version for LWs 31 and 32
Jul-20	MSEC1045-13-02	A	Draft for submission to landowner for LW W1-W2

References:-

	AS/NZS 4360:1999 Risk Management
	AS/NZS ISO 31000:2009 Risk Management – Principles and guidelines
MSO (2017)	Managing risks of subsidence – Guide WHS (Mines and Petroleum Sites) Legislation, NSW Department of Planning & Environment, Resources Regulator, Mine Safety Operations, February 2017.
MSEC (2019)	Tahmoor Coal - Longwalls W1 and W2 - Subsidence Predictions and Impact Assessments for Natural and Built Features due to the Extraction of the Proposed Longwalls W1 and W2 in Support of the Extraction Plan Application. (Report No. MSEC1019, Revision B, July 2019), prepared by Mine Subsidence Engineering Consultants.
Niche (2018)	675 Thirlmere Way, Picton – Statement of Heritage Impact. Niche Environment and Heritage, March 2018.
JMA (2018)	LW32 Structure Investigation Report: R0492 – Mill Hill: 675 Thirlmere Way, Picton, John Matheson and Associates, March 2018.
Tahmoor Coal (2019)	Risk Assessment Report – Infrastructure. Tahmoor North – Western Domain, Longwalls West 1 and West 2, April 2019.

1.0 INTRODUCTION	1
1.1. Background	1
1.2. No. 675 Thirlmere Way, Picton	1
1.3. Objectives	3
1.4. Scope	3
1.5. Limitations	4
1.6. Proposed mining schedule	4
1.7. Definition of active subsidence zone	4
1.8. Compensation	5
2.0 RISK MANAGEMENT METHOD	6
2.1. NSW Work Health & Safety Legislation	6
2.2. General	7
2.2.1. Consequence	7
2.2.2. Likelihood	7
2.2.3. Hazard	7
2.2.4. Method of assessment of potential mine subsidence impacts	7
3.0 SUBSIDENCE PREDICTIONS AND IMPACT ASSESSMENTS	8
3.1. Maximum predicted conventional subsidence parameters	8
3.1.1. Observed subsidence movements during the mining of Longwalls 31 and 32	13
3.2. Predicted strain	15
3.3. Managing public safety	16
3.4. Identification of subsidence hazards that could give risk to risks to health and safety	18
3.5. Risk assessment	18
3.6. Structures	20
3.7. Structural assessment	20
3.8. Heritage assessment	21
3.9. Services	21
3.10. External pavements, fences and gates	21
3.11. Dams	21
4.0 RISK CONTROL PROCEDURES	22
4.1. Structures Management Group	22
4.2. Development and selection of risk control measures	22
4.3. Avoidance and mitigation measures	22
4.4. Ground and structure monitoring measures	23
4.4.1. Structure surveys	23
4.4.2. Visual inspections	24
4.4.3. Structural inspections	24
4.5. Triggers and responses	25
4.6. Risk control procedures	25
5.0 REPORTING AND COMMUNICATION PLAN	27
5.1. Consultation, co-operation and coordination	27

5.2. SMG meetings	27
6.0 AUDIT AND REVIEW	28
7.0 RECORD KEEPING	28
8.0 CONTACT LIST	29
APPENDIX A. Drawings and Supporting Documentation	30

Tables

Tables are prefaced by the number of the chapter in which they are presented.

Table No.	Description	Page
Table 1.1	Longwall dimensions.....	1
Table 1.2	Schedule of mining.....	4
Table 3.1	Maximum predicted vertical subsidence, tilt and curvature for the structures at Mill Hill after the completion of LW W1	12
Table 3.2	Maximum predicted vertical subsidence, tilt and curvature for the structures at Mill Hill after the completion of LW W2	12
Table 3.3	Summary of the risk assessment.....	19
Table 3.4	Assessed impacts for the residential structures.....	20
Table 4.1	Risk control procedures	26

Figures

Figures are prefaced by the number of the chapter in which they are presented.

Figure No.	Description	Page
Fig. 1.1	Location of property relative to LW W1-W2	2
Fig. 1.2	Miller’s House (V06a).....	3
Fig. 1.3	Diagrammatic representation of active subsidence zone.....	5
Fig. 3.1	Predicted incremental conventional subsidence contours due to the extraction of LW W1	8
Fig. 3.2	Predicted cumulative conventional subsidence contours due to the extraction of LW W1-W2..	9
Fig. 3.3	Predicted total conventional subsidence contours after the extraction of Longwall 32.....	10
Fig. 3.4	Predicted total conventional subsidence contours after the extraction of LW W2	11
Fig. 3.5	Observed total subsidence and horizontal movement at Mill Hill after the completion of mining of LW32 as at 30 October 2019	13
Fig. 3.6	Development of subsidence, tilt and strain at Mill Hill as at 26 June 2020	14
Fig. 3.7	Distributions of the maximum measured tensile and compressive strains during the extraction of previous longwalls for survey bays located above solid coal	16
Fig. 3.8	Flowchart for subsidence impact management process	17
Fig. 4.1	Ground survey marks.....	24

Drawings

Drawings referred to in this report are included in Appendix A at the end of this report.

Drawing No.	Description	Revision
MSEC1045-13-02	Mill Hill Monitoring	01



Commercial in Confidence

- For more information
contact Tahmoor Coal

SIMEC

Level 28, 88 Phillip Street,
Sydney NSW 2000

Legal entity name goes here ABN: 00 000 000 000

T: +61 (0) 2 0000 0000

E: xxxxxxxx.xxxxxxx@simecgg.com

simec.com

MEMBER OF

